
From: Richard Kahn <[REDACTED]>
Sent: Wednesday, November 14, 2018 6:54 PM
To: Jeffrey Epstein
Subject: Fwd: LSJ Road Crew Bid

attached is what kyle sent which is incomplete as it does not include materials below, rebar, wood, mesh and trucking costs

will work with daphne and kyle to obtain

funny how brice says kyle is working on when you have been asking him for 3 weeks now..

Richard Kahn
HBRK Associates Inc.
575 Lexington Avenue 4th Floor
New York, NY 10022
[REDACTED]

Begin forwarded message:

From: Kyle reavis <[REDACTED]>
Subject: LSJ Road Crew Bid
Date: November 14, 2018 at 10:40:18 AM EST
To: Richard Kahn <[REDACTED]> Daphne Wallace <[REDACTED]>

Rich,

For us to self perform this we will need a 4 man crew. Since most of them will not have experience here I will be with them training them. Once we have our crew set our layout times will be cut significantly along with turnover time for mixing our truck.

Daphne can you call Heavy materials and see what our price is for the cement, stone and sand? This will determine our price per yard. Thank you!

Gym Road = 650' x 10' x 4" = 81 cubic yards 4000 PSI
 =nbsp; Total Weight of Cement / Sand / Gravel
 =nbsp; -----NEED TO PRICE THIS-----
 =nbsp; Cement - 49,491 lbs
 =nbsp; Sand - 117,450 lbs
 =nbsp; Stone - 129,600 lbs

=nbsp; Time Frame:
 =nbsp; 4 man crew- 5 day work = 1 week
 =nbsp; Total Prep = 2 weeks
 =nbsp; Pour days = 1 week
 =nbsp; Cutting = 1 week
 =nbsp; Total = 4 weeks

Pool Road = 250' x 10' x 4" + 31 Yards 4000 PSI
 =nbsp; -----NEED TO PRICE THIS-----
 =nbsp; Cement - 18,941 lbs
 =nbsp; Sand - 44,950 lbs
 =nbsp; Stone - 49,600 lbs

=nbsp; Time Frame:
 =nbsp; 4 man crew = 5 day work = 1 week
 =nbsp; Prep - 1 week
 =nbsp; Pour Time - 1 day
 =nbsp; Cutting - 3 days

Very Respectfully,

Kyle Reavis

=